

MAIN STREET PAVING SCHEDULE



Department of Public Works

The Town of Abingdon Department of Public Works has contracted with W-L Paving and Construction, Inc. for asphalt surface pavement replacement for the full width of **Main Street from Hutton Street to Church Street**. The work involves milling and removal of the top 1-1/2" of existing asphalt and replacement with new 1-1/2" surface course of asphalt. Pavement markings will then be placed on the new asphalt.

Current Schedule:

The work is currently scheduled to **start Sunday, May 18th, at approximately 7 PM**. The work will be done over five to six nights, from the hours of 7 PM to 7 AM. The duration of the work, and the actual nights that work takes place, can be affected by rain. Weather permitting, the work will progress as follows:

Night 1 : Mill the south side of Main Street, from the centerline to the curb

Night 2 : Mill the north side of Main Street, from the centerline to the curb

Night 3 : Resurface the south side of Main Street, from the centerline to the curb

Night 4 : Resurface the north side of Main Street, from the centerline to the curb

Night 5 : Pavement Markings installed (centerlines, stop bars, crosswalks, parking spaces)

Night 6 (if needed) : Pavement Markings installed (centerlines, stop bars, crosswalks, parking spaces)

The work will at times involve lane closures, detours, and rough unmarked road surface. Parking will be restricted for one entire side of Main Street, from Hutton Street to Church Street, on the side where work is being done on a particular night. The parking restriction will likely alternate each night. Signs and cones will be placed to define the parking restriction areas.

Town of Abingdon Contacts:

For questions regarding the work, contact John Dew or Gary Spry at 276-628-3167, or jdew@abingdon-va.gov or gspry@abingdon-va.gov.