

Town of Abingdon  
**INVITATION TO BID**  
**ADDENDA #1**  
**(Posted 09/04/2024)**



Project Title:

**HARRY L. COOMES RECREATION CENTER UPPER PARKING LOT**

**Bid Release Date: August 29, 2024**

**Bid Opening/Due Date: 10:00 AM on Tuesday, September 17, 2024**

**Courier or Hand Delivery Address:**

Michael Surrett  
Public Works Director  
Town of Abingdon  
299 Kings Mountain Drive  
Abingdon, Virginia 24210

**BASE BID SCHEDULE – REVISED**

**CORRECTED FORM FOR BID**

Note: All line markings for the handicap area will be WHITE.

BIDDER will complete the Work in accordance with the Contract Documents for the following price(s):

Item	Description	Estimated Quantity		Unit Price	Total Price
1.	ASPHALT, SM-9.5A	297	TON	\$	\$
2.	TACK COAT (.06 gal/sq. yd.) (3,409 sq. yds.)	205	GAL	\$	\$
3.	MILLING, 0"- 1.5"	2,198	SY	\$	\$
4.	Handicap spaces	7	EACH	\$	\$
5.	VDOT, TYPE.B CLASS I MARKING, 4", white parking lines, gore areas, center lines	1,846	LF	\$	\$
6.	VDOT, TYPE.B CLASS I <b>STOP MARKING</b>	66	LF	\$	\$
7.	VDOT, TYPE.B CLASS I <b>SINGLE ARROW</b>	7	EACH	\$	\$
8.	VDOT, TYPE.B CLASS I, 12" <b>CROSSWALK</b>	144	LF	\$	\$
9.	Mobilization		LS	\$	\$
10.	Maintenance of Traffic		LS	\$	\$
11.					
<b>Bid Quantities Total</b>				\$	

**TOTAL COST OF ALL BID ITEMS:** (\$ \_\_\_\_\_). (In figures)

\_\_\_\_\_  
(IN WORDS)

Bid prices in this contract for items containing PG 64-22 were developed using an f.o.b. price of \$\_\_\_\_\_ per imperial ton for PG 64-22. The latest industry quote available is attached and establishes the base asphalt cement price for the life of the project.

Bid prices in this contract for items containing PG 76-22 were developed using an f.o.b. price of \$\_\_\_\_\_ per imperial ton for PG 76-22. The latest industry quote available is attached and establishes the base asphalt cement price for the life of the project.

Price quotes signed by each supplier from which the Contractor proposes to obtain PG 64-22 and PG 76-22 shall be maintained by the successful bidder. These quotes shall be retained on site during the life of the Contract for review by the Town upon request.

THE ABOVE UNIT PRICES SHALL INCLUDE THE COSTS OF ALL ASPHALT WEDGING AROUND MANHOLES, VALVE BOXES, ETC., ALL TRAFFIC CONTROL, ALL MANHOLE AND VALVE BOX ADJUSTMENTS TO GRADE, ALL CLEAN-UP, ALL ASPHALT BERMS, AND OTHER ITEMS REQUIRED TO COMPLETE THE REQUIREMENTS AND INTENT OF THE CONTRACT AND AS STATED IN THE SCOPE OF WORK SECTION OF THESE BID DOCUMENTS.

**NOTE: The Town reserves the right to add or delete paving locations, from the approved list during the course of the contract. However, it is expected that the final quantities will be within plus or minus 25% of the amount bid. (See Special Provisions)**

_____ (Company)	_____ (Address)
_____ (Signed)	_____ (Date)
_____ (Written Name)	_____ (Business Phone No.)
_____ (Title)	_____ (Email address)

Virginia Contractor License Number: \_\_\_\_\_

# WORK SCHEDULE



## PAVEMENT PAVING AND PLANING LOCATIONS AND WORK SCOPE

### WORK SCHEDULE LOCATIONS

**Main Entrance Drive Aisle, Front parking lot, VDOT SM-9.5A (non-polishing aggregate).** (Approximately 1,166 Sq/Yds)

1. **Overlay/Resurface with 1.5" VDOT SM-9.5A (non-polishing aggregate).**
2. Full Width Mill and Remove 1.5" of existing asphalt as designated on attached map.
3. Mill and remove 1.5"-0" at seams and concrete curbing, as needed.
4. Be aware of electrical box during milling and paving (marked on map).
5. Stripe according to map.

**Circular Drive and Handicap Parking, VDOT SM-9.5A (non-polishing aggregate)** (Approximately 981 Sq/Yds)

1. **Overlay/Resurface with 1.5" VDOT SM-9.5A (non-polishing aggregate).**
2. Full Width Mill and Remove 1.5" of existing asphalt as designated on attached map.
3. Full Width Mill and Remove 1.5"-0" of existing asphalt at seams, concrete curbing and concrete sidewalks.
4. Stripe according to map. **White Line Markings.**

**Upper Parking Lot (at tennis court), VDOT SM-9.5A (non-polishing aggregate)** (Approximately 1313 Sq/Yds)

1. **Overlay/Resurface with 2.0" to 1.5" VDOT SM-9.5A (non-polishing aggregate).**
2. 2.0" overlay along sidewalk and curbing
3. 1.5" overlay through mid-section of parking aisle.
4. Mill and remove 1.5"-0" of existing asphalt at wedge for asphalt seams, marked on map.
5. Stripe according to map.

### **Work Schedule Notes:**

- See map attachment.
- Clean all areas of milling waste and asphalt waste during and immediately after these operations.
- Provide temporary pavement markings as directed by Town Engineer or their direct representative. VDOT Type A
- Provide/Replace permanent pavement markings as directed by Town Engineer or their direct representative. VDOT Type B Class 1